



# DAQ and Online

## WBS 1.3

S. Fuess, Fermilab

P. Slattery, U. of Rochester



# Introduction

---

- Outline
  - ◆ Organization chart
  - ◆ Structure of DAQ/Online system
  - ◆ Run II b requirements and changes
  - ◆ Details of component upgrades
  - ◆ Cost, Effort, Risk Analysis



# Organization

D0 Run II b Project  
J. Kotcher, Project Manager  
R. Partridge, Deputy; V. O'Dell, Associate; W. Freeman, Assistant  
M. Johnson, Technical Coordinator  
C. Yoshikawa, Budget Officer; T. Erickson, Administration

Online group has excellent record of providing working network, host, and control systems, fully operational since earliest days of Run II a commissioning


- Much credit goes to Computing Division for their contributions

In 12/2001 group reorganized to include new DAQ (readout and event building) initiative

- Successfully designed and installed state-of-the-art commodity-based DAQ system now in active use
  - kHz capable system ready for Run II b

Online group is also represented in DO's Computing and Run II a Operations organizational structure

- Integrated Run II a / II b / Computing planning





# Structure of DAQ/Online

## The DAQ/Online system consists of:

### ◆ Event path:

- DAQ and Online network
- Single Board Computers (SBCs) in VME readout crates
- Level 3 software filter farm
- Host systems for data transport and logging

### ◆ Control and Monitoring:

- Control room systems
- Event data monitoring systems
- Slow control system, including VME processors

### ◆ Infrastructure:


- Database servers
- File servers

### ◆ Software associated with the above

- **SOFTWARE architecture is unchanged for Run II b**




# Structure of DAQ/Online




continued...

**HARDWARE architecture is **unchanged** for Run IIb**  
**But many components **change****



# Structure of DAQ/Online





# Run I I b Requirements

---

- Maintain adequate Level 3 software trigger rejection in a more complex environment
- Provide capacity for higher peak recorded event rate (~100 Hz)
- Maintain reliable computing infrastructure



# Changes for Run II b

- **Systems to be discussed**
  - ◆ 1.3.1 Level 3 filter farm processors
  - ◆ 1.3.2 Host systems
    - ◆ 1.3.2.4 Storage systems
    - ◆ 1.3.2.6 DAQ hosts
    - ◆ 1.3.2.7 ORACLE database systems
    - ◆ 1.3.2.8 File servers
  - ◆ 1.3.3 Control systems

- **Manage complete Run II effort with proper tools:**

- TDR includes Run II a plans
- ◆ MS Project schedule for resource allocation includes Run II a effort
- ◆ Focus on Run II b in this talk

Any costs shown  
are unburdened  
FY02 \$



# Component Details

- Level 3

- ◆ Processing time requirements:

- ◆ At  $2 \times 10^{31} \text{ cm}^{-2}\text{s}^{-1}$  current filter code, including global tracking, requires ~300 msec/event on 1 GHz PIII
  - Maps to 250 msec/event for single interaction, equivalent to 10 SpecInt95 secs/event
- ◆ Extrapolation depends upon complexity of event, a function of luminosity and bunch crossing time
  - For L3 filter code, processing most dependent upon occupancy. Assume linear rise in requirements with number of interactions.
  - For 1 primary + 5 background interactions per crossing and 1 KHz L3 input rate, predicted CPU requirement is 60K SpecInt95



# Component Details

- **Level 3 acquisition plan:**
  - ◆ **Purchase systems as late as possible to take advantage of Moore's law**
    - Assuming 1.6x CPU improvement per year
  - ◆ **96 nodes @ ~\$2.2K = \$210K, purchased in FY05**
    - Includes infrastructure (network, racks, power)
  - ◆ **Combined with Run I I a systems, this will give capacity of 70K SpecInt95**



# Component Details

- **Host systems and storage**

- ◆ **Fibre channel SAN with RAID arrays for Database and File Servers, JBOD for data buffer disks**

- ◆ 1.3 TB RAID, 4 TB JBOD (48 hours of buffer)
- ◆ FC fabric infrastructure, highly available systems
- ◆ \$103K with early development (FC on Linux) effort, then purchase FY04

- ◆ **Redundant (primary/secondary) small servers (4-8 CPU)**

- ◆ Data logging system, ORACLE database system, and File server system
- ◆ \$144K with Secondary server purchase FY04, then Primary server purchase FY05
  - As late as possible to get best performance



# Component Details

- **Control system processor upgrades**
  - ◆ **Run IIa systems include ~100 embedded VME processors for downloading, control, monitoring, and diagnostic readout of the detector**
    - Use the EPICS control system
    - Motorola 68K and PowerPC family
  - ◆ **Concerned with longevity**
    - Spares may not satisfy extended Run II b needs
    - Replacement processors may not be available in Run II b era
  - ◆ **~1/2 are fully loaded with present monitoring functions**
    - We wish to do more complete monitoring in Run II b
  - ◆ **Strategy is to replace ~50% of processors with new architecture**
    - Following EPICS community advancements
    - Target those with largest processing loads
    - Remainder become spares
    - 53 nodes @ \$2.8K each = \$148K



# Component Details

- **SiDet test stand support**
  - ◆ **1% and 10% test stands at SiDet are “micro” DAQ/Online systems**
    - ◆ Require SBC (readout) and Host/Control/Monitor Linux node
    - ◆ Require control system processor (to be supplied from operational spares)
  - ◆ **DAQ/Online group will supply experts to assist in commissioning these systems**
    - ◆ Requires small fraction of experts' time during installation and operation
    - ◆ Loaded into MS Project schedule




# M&S Cost Summary

Equipment	M&S Cost	Contingency		Total Cost
		%	Cost	
<b>Level 3 filter nodes</b>	<b>210</b>			<b>357</b>
Nodes, racks, power supplies, cables	210	70	147	357
<b>Fibre Channel SAN</b>	<b>60</b>			<b>90</b>
Hubs, cables	20	50	10	30
Fibre Channel JBOD buffer disk	40	50	20	60
<b>RAID storage array</b>	<b>43</b>			<b>65</b>
FC RAID controllers	10	50	5	15
Disk crates, rack	15	50	8	23
Hot-swappable disks	18	50	9	27
<b>DAQ HOST system</b>	<b>52</b>			<b>78</b>
Primary high-end server	32	50	16	48
Secondary mid-range server	20	50	10	30
<b>Database System</b>	<b>52</b>			<b>78</b>
Primary high-end server	32	50	16	48
Secondary mid-range server	20	50	10	30
<b>File Server system</b>	<b>40</b>			<b>60</b>
Primary mid-range server	20	50	10	30
Secondary mid-range server	20	50	10	30
<b>Control System</b>	<b>148</b>			<b>185</b>
Processor upgrades	148	25	37	185
<b>Total</b>	<b>605</b>		<b>308</b>	<b>913</b>

Unburdened  
FY02 K\$

Contingency guidance from Project Management Plan



# Effort

- Fully resource loaded into MS Project schedule
- Exploiting developed expertise to meet Run II b goals
- Mostly “fractions of” personnel who are otherwise dedicated to Run II operations

•Largest components:

- Strategic planning (PHYSF)
- System installation and management (COMPF)
- ORACLE database migration (COMPF)
- Control system upgrades (PHYSF,COMPF)

◆ Net technical labor cost ~\$178K



# Risk Analysis

- These elements are pointed out:
  - ◆ Cost
    - Required number of Level 3 filter nodes a function of the interaction environment, detector performance, and software performance. 70% contingency to address possible need for purchase of more nodes.
    - Details of future VME processors unknown. Address risk with possible scope reduction.
  - ◆ Schedule
    - No significant risks
  - ◆ Scope
    - No significant risks
  - ◆ Technical
    - No significant risks



# DAQ / Online Summary

---

- Building upon fundamentally solid hardware and software system architectures
  - ◆ We know what to do
- System constructed of commodity components by experienced group
  - ◆ We know how to do it
- Project addresses requirements for Run II b capabilities and system longevity
  - ◆ We're ready to go!